



NOTES

1. IT IS THE RESPONSIBILITY OF THE CONSULTANT OR CONTRACTOR, TO CONFIRM THAT THE CONTROLS SELECTION IS CORRECT PRIOR TO INSTALLATION.
2. DO NOT SCALE FROM THIS DRAWING. ALL DIMENSIONS SHOULD BE CHECKED ON SITE.
3. THIS DRAWING IS FOR INDICATION ONLY.
4. ALL CONTROLS COMPONENTS SHOULD BE FITTED INSIDE A SUITABLE ENCLOSURE.
5. ALL CABLES MUST BE SIZED ACCORDING TO CURRENT

LEGEND

- | | |
|----|-------------------------------|
| 1 | Live Wire on Indoor Unit |
| 2 | Neutral Wire on Indoor Unit |
| 3 | Serial Wire on Indoor Unit |
| L | Live Wire on Outdoor Unit |
| N | Neutral Wire on Outdoor Unit |
| AB | Remote Controller Connections |

<p>Cool Designs Ltd</p>	<p>Drawing Prepared For</p>	<p>Title CDL-BMS01 LEAD CONNECTED TO INDOOR UNIT TO PROVIDE EXTERNAL REMOTE CONTROLLER LOCK OUT</p>	
<p>Cool Designs Ltd North Hylton Enterprise Park Hepworth Rd Sunderland SR5 3JT Tel: 0191 540 0004 Fax: 0191 540 0000 email: sales@cooldesigns.co.uk</p>	<p>Project STANDARD ELECTRICAL SCHEMATIC SHOWING CDL-BMS01 LEAD CONNECTED TO DI SPLIT TO PROVIDE REMOTE CONTROLLER LOCK OUT</p>	<p>Drawn By</p>	<p>Checked By</p>
		<p>Scale NTS</p>	<p>Date Drawn 10/11/07</p>
		<p>Drawing No.</p>	